

**Order No. 3500778758**

Created On 11.03.2026



|                                                                                                                                                                                                                                   |                                                                                                                                                   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|
| Supplier : 201785_FJARSAP<br>201785-REFTECH JAYA OPTIMA PT<br>KOMP NEGLA KENCANA RESIDENCE BLOK B NO 2 RT/RW 003/005<br>PASANGGRAHAN UJUNGBERUNG<br>BANDUNG, BANDUNG<br>Indonesia , 40617<br>IRENE@REFTECH.ID<br>+62 081320583277 | Bill To:<br>PT. Fajar Surya Wisesa Tbk.<br>Jl. Abdul Muis No. 32<br>Jakarta, Indonesia<br>Tel No.: (6221) 344 1316<br>Tax ID: 0013 2623 6509 2000 |
| Requester: coupa.fajar14 coupa.fajar14<br>Requester AD User: RISDIANTO -                                                                                                                                                          | Ship To:<br>8020_FSW West Cikarang<br>Jl. Kampung Gardu Sawah RT.001/1-1, Desa Kalijaya, Cikarang Barat<br>Bekasi, 17520<br>Indonesia             |
| Payment Terms:<br>90 days after baseline date                                                                                                                                                                                     |                                                                                                                                                   |

| ITEM | DESCRIPTION                             | Delivery Date | Qty | Unit | Unit Price      | Amount          |
|------|-----------------------------------------|---------------|-----|------|-----------------|-----------------|
| 1    | SVC_CONTRACT ALL COMP&AIR DRYER (MARET) | 30.04.2026    | 1.0 | AU   | 100,000,000 IDR | 100,000,000 IDR |

## Material PO Text:

SVC\_CONTRACT ALL COMP&amp;AIR DRYER (MARCH 2026)

Maret : IDR. 100,000,000

Note: Additional overtime cost outside of working hours (per person) : IDR. 45,000/Hour

## # Working Hour &amp; Total Man Power per day :

Monday-Friday : pk 08.00 – pk 16.00 ( 7 Hour) - 4 Person

Saturday, Sunday &amp; Nationality day : pk 08.00 – pk 14.00 ( 5 Hour) - 2 Person

Note: For Eid Mubarak Holiday Manpower will be off 2 days (The days and H+1)

## # Scope of work

## Air Compressor :

## • Daily Activities

1. Checking working pressure and ensuring it meets specifications
2. Checking air temperature from the compressor
3. Checking compressor oil level (Ok / Not Ok)
4. Checking running hour and loading hour of the compressor unit
5. Checking indicator or control panel if errors or alarms (Report at Issue)
6. Checking for air leaks on system (Ok / Not Ok)
7. Ensuring there is no abnormal noise or vibration when the compressor is operating (Report at Issue)

## • Weekly Activities

1. Checking vibration airend / screw.
2. Checking voltage (R/S/T).
3. Checking running ampere of the compressor unit (R/S/T).
4. Cleaning cooler from dust or cleaning by water
5. Testing automatic drain system (Eco Drain) to detect blockages or malfunctions (Ok / Not Ok)
6. Checking condition coupling or V-belt and replace when damage is found
7. Cleaning Compressor unit & Cleaning area compressor

## • Monthly Activities

1. Greasing main motor (2000 jam) (Report at Maintenance Log)
2. Cleaning air filter from dust. (Report at Maintenance Log)

## Air Dryer :

## • Daily Activities

1. Cleaning air filter from dust. Checking the temperature/dewpoint indicator.
2. Checking inlet and outlet air temperatures to ensure all OK
3. Checking panel indicators from errors or alarms (OK / Not OK).
4. Checking condensate drain lines (Eco Drain) to ensure they are not blocked (OK / Not OK).
5. Visual check for air or refrigerant leaks in the system (OK / Not OK).
6. Visual check to ensure the condenser fan is running normal (OK / Not OK).

## • Weekly Activities

1. Checking voltage (R/S/T).
2. Checking running ampere of refrigerant compressor (R/S/T).
3. Cleaning condenser from dust or dirt using air.

**Order No. 3500778758**

Created On 11.03.2026



| ITEM | DESCRIPTION | Delivery Date | Qty | Unit | Unit Price | Amount |
|------|-------------|---------------|-----|------|------------|--------|
|------|-------------|---------------|-----|------|------------|--------|

- |  |                                                                                                                  |  |  |  |  |  |
|--|------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|
|  | 4. Testing automatic drain system to detect blockages or malfunctions.                                           |  |  |  |  |  |
|  | 5. Checking pre and after filters (OK / Not OK).                                                                 |  |  |  |  |  |
|  | • Monthly Activities                                                                                             |  |  |  |  |  |
|  | 1. Check pressure in the refrigeration system to ensure it is within normal (OK / Not OK)                        |  |  |  |  |  |
|  | 2. Check and clean the strainers on the timer drain in the dryer, inline filter, and receiver tank (OK / Not OK) |  |  |  |  |  |

## SCOPE OF WORK FOR CORRECTIVE MAINTENANCE AIR COMPRESSOR :

## INCLUDE :

1. Replace oil filter
2. Replace air filter.
3. Replace oil separator (Max 75KW – CS Series)
4. Add oil / replace compressor oil.
5. Greasing motor every 2000 hours.
6. Replace inlet valve maintenance kit. (Max 75KW – CS Series)
7. Replace venting oil valve maintenance kit.
8. Replace pressure gage on the separator tank.
9. Replace eco drain repair kit.
10. Replace gaskets on leaking connections.
11. Replace leaking seals/fittings in the oil system.
12. Repair/Replace clogged or malfunctioning automatic drain system.
13. Replace temperature sensors on the screw and separator tank.
14. Replace pressure sensors on the separator tank and unit output.
15. Replace electrical components such as relays, contactors, and emergency stops.
16. Replace burned cables in the compressor unit panel.
17. Replace blown electrical fuses in the control panel.

## SCOPE OF WORK FOR CORRECTIVE MAINTENANCE AIR DRYER :

## INCLUDE :

1. Cleaning condensate drain (NOT Include Area Production)
2. Replace temperature or pressure sensors.
3. Replace pressure gauges on the unit that are faulty or leaking.
4. Replace filter driers equipped with ball valves in/out.
5. Replace drain hoses that are leaking or cracked.
6. Repair loose electrical wire connections at the terminals.
7. Replace blown electrical fuses in the control panel.
8. Clean the condensate filter in the automatic drainage system.
9. Inspect and lubricate the fan motor if necessary.
10. Tightening air pipe connections to prevent small leaks.
11. Add refrigerant if necessary.
12. Clean the dryer unit's cabin/body for better visibility.

Contract Duration (01 March 2026 - 31 March 2026)

TOP: 90 HARI SETELAH TANDA TERIMA FAKTUR + BERITA ACARA LENGKAP

Addition Text:

Supplier Part Number:

Plant: 8020\_FSW West Cikarang

Delivery Text:

MARCH 2026

Buyer: INDRA HARYONO

E-mail: indra.haryono@fajarpaper.com

PR No. 917656

Reference Document Item: SAP-SAPMO\_1100074255\_00010

Inco Terms: FRA\_Franco\_FJARSAP

Material Group: NS00\_Non-Stocked Service



**Order No. 3500778758**  
Created On 11.03.2026



|                                 |                    |
|---------------------------------|--------------------|
| Total PO Amount                 | 100,000,000.00 IDR |
| Total VAT Amount                | 11,000,000.00 IDR  |
| Total PO Amount (Including VAT) | 111,000,000.00 IDR |

This document is issued and approved electronically by Buyer Authorized Person via our Buyer System.  
Authorized signature is not required.  
No Assignment of Rights and Obligations  
Please refer to our PO Number in your delivery note, invoice and any other relevant documents.  
UPON THE ISSUANCE OF THIS PURCHASE ORDER, SELLER SHALL ACKNOWLEDGE NO LATER THAN THREE (3) BUSINESS DAYS, OTHERWISE THE PURCHASE ORDER SHALL BE DEEMED ACCEPTED.