

**Order No. 3500791367**

Created On 31.03.2026



Supplier : 201785_FJARSAP 201785-REFTECH JAYA OPTIMA PT KOMP NEGLA KENCANA RESIDENCE BLOK B NO 2 RT/RW 003/005 PASANGGRAHAN UJUNGBERUNG BANDUNG, BANDUNG Indonesia , 40617 IRENE@REFTECH.ID +62 081320583277	Bill To: PT. Fajar Surya Wisesa Tbk. Jl. Abdul Muis No. 32 Jakarta, Indonesia Tel No.: (6221) 344 1316 Tax ID: 0013 2623 6509 2000
Requester: coupa.fajar14 coupa.fajar14 Requester AD User: RISDIANTO -	Ship To: 8020_FSW West Cikarang Jl. Kampung Gardu Sawah RT.001/1-1, Desa Kalijaya, Cikarang Barat Bekasi, 17520 Indonesia
Payment Terms: 90 days after baseline date	

ITEM	DESCRIPTION	Delivery Date	Qty	Unit	Unit Price	Amount
1	SVC_CONTRACT ALL COMP&AIR DRYER (APRIL)	31.05.2026	1.0	AU	85,000,000 IDR	85,000,000 IDR

Material PO Text:

SVC_CONTRACT ALL COMP&AIR DRYER (APRIL 2026)

April : IDR. 85,000,000

Note: Additional overtime cost outside of working hours (per person) : IDR. 45,000/Hour

Working Hour & Total Man Power per day :

Monday-Friday : pk 08.00 – pk 16.00 (7 Hour) - 4 Person

Saturday, Sunday & Nationality day : pk 08.00 – pk 14.00 (5 Hour) - 2 Person

Note: For Eid Mubarak Holiday Manpower will be off 2 days (The days and H+1)

Scope of work

Air Compressor :

• Daily Activities

1. Checking working pressure and ensuring it meets specifications
2. Checking air temperature from the compressor
3. Checking compressor oil level (Ok / Not Ok)
4. Checking running hour and loading hour of the compressor unit
5. Checking indicator or control panel if errors or alarms (Report at Issue)
6. Checking for air leaks on system (Ok / Not Ok)
7. Ensuring there is no abnormal noise or vibration when the compressor is operating (Report at Issue)

• Weekly Activities

1. Checking vibration airend / screw.
2. Checking voltage (R/S/T).
3. Checking running ampere of the compressor unit (R/S/T).
4. Cleaning cooler from dust or cleaning by water
5. Testing automatic drain system (Eco Drain) to detect blockages or malfunctions (Ok / Not Ok)
6. Checking condition coupling or V-belt and replace when damage is found
7. Cleaning Compressor unit & Cleaning area compressor

• Monthly Activities

1. Greasing main motor (2000 jam) (Report at Maintenance Log)
2. Cleaning air filter from dust. (Report at Maintenance Log)

Air Dryer :

• Daily Activities

1. Cleaning air filter from dust. Checking the temperature/dewpoint indicator.
2. Checking inlet and outlet air temperatures to ensure all OK
3. Checking panel indicators from errors or alarms (OK / Not OK).
4. Checking condensate drain lines (Eco Drain) to ensure they are not blocked (OK / Not OK).
5. Visual check for air or refrigerant leaks in the system (OK / Not OK).
6. Visual check to ensure the condenser fan is running normal (OK / Not OK).

• Weekly Activities

1. Checking voltage (R/S/T).
2. Checking running ampere of refrigerant compressor (R/S/T).
3. Cleaning condenser from dust or dirt using air.

**Order No. 3500791367**

Created On 31.03.2026



ITEM	DESCRIPTION	Delivery Date	Qty	Unit	Unit Price	Amount
	4. Testing automatic drain system to detect blockages or malfunctions. 5. Checking pre and after filters (OK / Not OK). • Monthly Activities 1. Check pressure in the refrigeration system to ensure it is within normal (OK / Not OK) 2. Check and clean the strainers on the timer drain in the dryer, inline filter, and receiver tank (OK / Not OK)					

SCOPE OF WORK FOR CORRECTIVE MAINTENANCE AIR COMPRESSOR :

INCLUDE :

1. Replace oil filter
2. Replace air filter.
3. Replace oil separator (Max 75KW – CS Series)
4. Add oil / replace compressor oil.
5. Greasing motor every 2000 hours.
6. Replace inlet valve maintenance kit. (Max 75KW – CS Series)
7. Replace venting oil valve maintenance kit.
8. Replace pressure gage on the separator tank.
9. Replace eco drain repair kit.
10. Replace gaskets on leaking connections.
11. Replace leaking seals/fittings in the oil system.
12. Repair/Replace clogged or malfunctioning automatic drain system.
13. Replace temperature sensors on the screw and separator tank.
14. Replace pressure sensors on the separator tank and unit output.
15. Replace electrical components such as relays, contactors, and emergency stops.
16. Replace burned cables in the compressor unit panel.
17. Replace blown electrical fuses in the control panel.
18. Install sigma control
19. Replace control line kit.
20. Replace damaged/leaking flexible air and oil hoses.
21. Replace Hour Meter.
22. Replace Solenoid Loading Unloading Valve.
23. Replace Membrane Oil Venting Valve.
24. Replace Membrane Aux. Venting Valve.
25. Cleaning Stainer Scavenging valve.
26. Replace Sensor Oil Filter.
27. Replace Thermostatic Valve

SCOPE OF WORK FOR CORRECTIVE MAINTENANCE AIR DRYER :

INCLUDE :

1. Cleaning condensate drain (NOT Include Area Production)
2. Replace temperature or pressure sensors.
3. Replace pressure gauges on the unit that are faulty or leaking.
4. Replace filter driers equipped with ball valves in/out.
5. Replace drain hoses that are leaking or cracked.
6. Repair loose electrical wire connections at the terminals.
7. Replace blown electrical fuses in the control panel.
8. Clean the condensate filter in the automatic drainage system.
9. Inspect and lubricate the fan motor if necessary.
10. Tightening air pipe connections to prevent small leaks.
11. Add refrigerant if necessary.
12. Clean the dryer unit's cabin/body for better visibility.
13. Panel Inspection Using a Thermal Imager.
14. Coating Pipe All Unit Air Dryer.
15. Add Refrigerant if needed.
16. Replacement Filter Element.
17. Cleaning Solenoid Valve Drainage System.
18. Replace New Condensate Drain.
19. Replace Condensate Piping.

Contract Duration (01 April 2026 - 30 April 2026)

TOP: 90 HARI SETELAH TANDA TERIMA FAKTUR + BERITA ACARA LENGKAP

Addition Text:

Supplier Part Number:

Plant: 8020_FSW West Cikarang

Delivery Text:



Order No. **3500791367**
Created On 31.03.2026



ITEM	DESCRIPTION	Delivery Date	Qty	Unit	Unit Price	Amount
	APRIL 2026					
	Buyer: INDRA HARYONO E-mail: indra.haryono@fajarpaper.com PR No. 917658 Reference Document Item: SAP-SAPMO_1100074256_00010 Inco Terms: FRA_Franco_FJARSAP Material Group: NS00_Non-Stocked Service					

Total PO Amount	85,000,000.00 IDR
Total VAT Amount	9,350,000.00 IDR
Total PO Amount (Including VAT)	94,350,000.00 IDR

This document is issued and approved electronically by Buyer Authorized Person via our Buyer System.
Authorized signature is not required.
No Assignment of Rights and Obligations
Please refer to our PO Number in your delivery note, invoice and any other relevant documents.
UPON THE ISSUANCE OF THIS PURCHASE ORDER, SELLER SHALL ACKNOWLEDGE NO LATER THAN THREE (3) BUSINESS DAYS, OTHERWISE THE PURCHASE ORDER SHALL BE DEEMED ACCEPTED.